

CORRIGENDUM No: 1

to the

TENDER DOSSIER

Publication Ref: 0205-136, 2007CB16IPO007-2012-3-79/04

Subject: Construction of multimedia centre

Location – Stip

The Tender Dossier is corrected or modified as follow:

4. Volume 4 BoQ Lot 1 Section: C. CIVIL WORKS / ГРАДЕЖНИ РАБОТИ

C.5	OTHER MASONRY WORKS
------------	----------------------------

Instead of:

39	Making a horizontal hydro isolation, i.e. elastomeric bitumen membrane with polyester fabric 3x4mm, welded				
40	Making a vertical hydro isolation, i.e. elastomeric bitumen membrane with polyester fabric 3x4mm, welded				
41	Making a hydro isolation i.e. elastomeric bitumen membrane with polyester fabric 3x4mm, welded around the foundations				
42	Making a steam dam i.e. elastomeric bitumen membrane with polyester fabric d=4mm, welded				
43	Preparing a horizontal hydro isolation coating				
44	Preparing a vertical hydro isolation coating				
45	Fabrication and installation of ceiling metal construction and gypsum board panels, m2 314,46				
46	Fabrication and installation of metal construction and gypsum board panels covered with carpet, on a wall				
47	Fabrication and installation of ceiling metal construction and acoustic gypsum cardboard panels, in horizontal projection m2 198,45				

Read:

39	Making a horizontal hydro isolation, i.e. elastomeric bitumen membrane with polyester fabric 3x4mm, welded	m2	473,5		
40	Making a vertical hydro isolation, i.e. elastomeric bitumen membrane with polyester fabric 3x4mm, welded	m2	143,52		
41	Making a hydro isolation i.e. elastomeric bitumen membrane with polyester fabric 3x4mm, welded around the foundations	m2	124,32		
42	Making a steam dam i.e. elastomeric bitumen membrane with polyester fabric d=4mm, welded	m2	426,46		
43	Preparing a horizontal hydro isolation coating	m2	16,41		
44	Preparing a vertical hydro isolation coating	m2	31,5		
45	Fabrication and installation of ceiling metal construction and gypsum board panels, m2 314,46	m2	314,46		
46	Fabrication and installation of metal construction and gypsum board panels covered with carpet, on a wall	m2	260,5		
47	Fabrication and installation of ceiling metal construction and acoustic gypsum cardboard panels, in horizontal projection m2 198,45	m2	198,45		

4. Volume 4 BoQ Lot 1 Section: C. CIVIL WORKS / ГРАДЕЖНИ РАБОТИ

C.10	<u>CARPENTRY WORKS (according to the scheme of the carpentry)</u>
-------------	--

Instead of:

44	<u>Procurement and instalation of interior Wooden doors with dimensions :</u>	-	-	-	-
-	<u>position A</u>	____ No.	4	-	-
-	<u>position B</u>	____ No.	2	-	-
-	<u>position C</u>	No.	7	-	-
-	<u>position D</u>	No.	3	-	-
-	<u>position E</u>	No.	1	-	-
45	<u>procurement and installation of compartments with doors for a toilet pos No.6</u>	No.	6	-	-
<u>TOTAL CARPENTRY WORKS</u>					-

Read:

<u>44</u>	<u>Procurement and instalation of interior Wooden doors with dimensions :</u>	-	-	-	-
-	<u>position A</u> 175/220	<u>No.</u>	<u>4</u>	-	-
	<u>position B</u> 155/220	<u>No.</u>	<u>2</u>	-	-
	<u>position C</u> 90/220	<u>No.</u>	<u>7</u>	-	-
	<u>position D</u> 80/220	<u>No.</u>	<u>3</u>	-	-
	<u>position E</u> 110/220	<u>No.</u>	<u>1</u>	-	-
<u>45</u>	<u>procurement and installation of compartments with doors for a toilet pos No.6 90+160/200</u>	<u>No.</u>	<u>6</u>	-	-
<u>TOTAL CARPENTRY WORKS</u>					-

4. Volume 4 BoQ Lot 1 Section: C. CIVIL WORKS / ГРАДЕЖНИ РАБОТИ

C.13	<u>LOCKSMITH WORKS</u>
-------------	-------------------------------

Instead of:

<u>53</u>	<u>Preparation and installation of a fence on the stairs of anodized aluminum profiles m1 13,50</u>	<u>m1</u>	<u>13,5</u>	-	-
<u>54</u>	<u>PVC DOORS AND WINDOWS (according to the scheme of the carpentry)</u>	-	-	-	-
-	<u>position 1</u>	<u>pieces</u>	<u>6</u>	-	-
	<u>position 2</u>	<u>pieces</u>	<u>3</u>	-	-
	<u>position 3</u>	<u>pieces</u>	<u>1</u>	-	-
	<u>position 4</u>	<u>pieces</u>	<u>1</u>	-	-
	<u>position 5</u>	<u>pieces</u>	<u>1</u>	-	-
	<u>position 6</u>	<u>pieces</u>	<u>1</u>	-	-
	<u>position 7</u>	<u>pieces</u>	<u>1</u>	-	-
	<u>position 8</u>	<u>pieces</u>	<u>1</u>	-	-
	<u>position 9</u>	<u>pieces</u>	<u>3</u>	-	-
	<u>position 11</u>	<u>pieces</u>	<u>2</u>	-	-
	<u>position 15</u>	<u>pieces</u>	<u>2</u>	-	-

<u>55</u>	<u>Preparation and installation of doors of plastic profile with glass and double thermopane glass</u>	-	-	-	-
-	<u>position 10</u>	<u>pieces</u>	<u>1</u>	-	-
	<u>position 12</u>	<u>pieces</u>	<u>1</u>	-	-
	<u>position13</u>	<u>pieces</u>	<u>1</u>	-	-
	<u>position 14</u>	<u>pieces</u>	<u>1</u>	-	-
	<u>position 16</u>	<u>pieces</u>	<u>1</u>	-	-
	<u>position 17</u>	<u>pieces</u>	<u>1</u>	-	-
<u>TOTAL LOCKSMITH WORKS</u>					

Read:

<u>53</u>	<u>Preparation and installation of a fence on the stairs of anodized aluminum profiles m1 13,50</u>	<u>m1</u>	<u>13,5</u>	-	-
<u>54</u>	<u>PVC DOORS AND WINDOWS (according to the scheme of the carpentry)</u>	-	-	-	-
-	<u>position 1</u> 263/200	<u>pieces</u>	<u>6</u>	-	-
	<u>position 2</u> 350/139	<u>pieces</u>	<u>3</u>	-	-
	<u>position 3</u> 180/139	<u>pieces</u>	<u>1</u>	-	-
	<u>position 4</u> 260/139	<u>pieces</u>	<u>1</u>	-	-
	<u>position 5</u> 260/139	<u>pieces</u>	<u>1</u>	-	-
	<u>position 6</u> 250/60	<u>pieces</u>	<u>1</u>	-	-
	<u>position 7</u> 197/60	<u>pieces</u>	<u>1</u>	-	-
	<u>position 8</u> d100	<u>pieces</u>	<u>1</u>	-	-
	<u>position 9</u> 85/220	<u>pieces</u>	<u>3</u>	-	-
	<u>position11</u> 361/150	<u>pieces</u>	<u>2</u>	-	-
	<u>position 15</u> 140/140	<u>pieces</u>	<u>2</u>	-	-
<u>55</u>	<u>Preparation and installation of doors of plastic profile with glass and double thermopane glass</u>	-	-	-	-
-	<u>position 10</u> 80/220	<u>pieces</u>	<u>1</u>	-	-
	<u>position 12</u> 110/220	<u>pieces</u>	<u>1</u>	-	-
	<u>position13</u> 175/220	<u>pieces</u>	<u>1</u>	-	-

	<u>position 14</u>	310/368	<u>pieces</u>	<u>1</u>	-	-
	<u>position 16</u>	90/220	<u>pieces</u>	<u>1</u>	-	-
	<u>position 17</u>	140/300	<u>pieces</u>	<u>1</u>	-	-
TOTAL LOCKSMITH WORKS						

Following items are added to the Tender Dossier:

Section: EQ. Equipment / Оprema					
Item Поз	Description of works Опис на работи	Unit Мерка	QTY Колич.	Unit Rate (EUR) Един.цена	Amount (EUR) Вк.цена
EQ.1	Equipment				
214	Delivery and instalation of theater seats	No.	148		
215	Delivery and instalation of office chairs	No.	120		
216	Delivery and instalation of work tables	No.	60		
Total Equipment					
Total Equipment (Exclusive of VAT and other taxes) :					

All other terms and conditions of the contract notice remain unchanged. The above alterations and /or corrections to the Tender Dossier are integral part of the Tender Dossier.